(10) The contractor is responsible for all accidents to workmen, etc., on the work, and he must take precaution against all risk of accidents and, if necessary, provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

23. The Mysore Cement and Mysore Steel will have to be used in the construction.

Abstract estimate for constructing a high level causeway across the Gundlu river along Kabbahalli road from 3/117 of Bangalore-Nilgiri Road, Gundlupet Taluk.

No.	Items of works	Per	Quantity	Rate	Rate in words
	I. Construction of a bridge of 3 vents 20′×6′ with steel girders.			Rs. a. p.	Rs.
1	Excavating foundation in mixed soil of sand and clay and putting the same to bank with watering and consolidation	C.yd.	300		
2	Stone jelly in surki mortar	C.ft.	906		
3	Size stone in surki mortar	,,	5,200		
4	Pointing with cement mortar 1 : 3	Sqr.	18.00		
5	Putting cement concrete bearing slabs 1 : 2 : 4 below girders	C.ft.	25		
6	Providing and fixing B. S. S., R. S. joists 13″×5″×35 lbs. with two coats of non-corrosive paint, including carting to site and hoisting charges complete	Cwts.	43⅛		
7	Providing and putting up R.C.C. decking (1 : 2 : 4) for a total thickness of 8″ including a wearing coat of 1½″ with necessary scaffolding, etc., complete as per specification	C.ft.	552		
8	Providing and fixing hand railing 1½″ dia. G. I. pipe two lines with L iron verticles fixed in R.C.C. slab and masonry	R.ft.	204		
9	Cement concrete paving with 3″ of cement concrete 1 : 4 : 8 at bottom with 2″ of wearing coat of 1 : 2 : 4 at top to a total thickness of 5″ to a width of 8′	C.ft.	207		
10	New rough stone revetment with jelly backing including an average lead of 1½ miles	C.yd.	161		
11	Earthwork excavation for stone work and putting the spoil to bank including watering and consolidation	C.yd.	123		
	II. Forming approaches.				
1	Earthwork excavation putting the soil to bank including watering and consolidation	C.yd.	300		
2	New rough stone revetment with jelly backing including an average lead of 1½ miles	,,	418		
3	Paving 3″ cement concrete 1 : 4 : 8 at bottom with 2″ of wearing coat of 1 : 2 : 4 at top to a total thickness of 5″ for the track portions 8′ wide for the roadway	C.ft.	720		
4	Providing and fixing burnt stone toe slabs 6″ thick	S.ft.	300		
5	Providing and fixing pin slabs 3′×1½×6″ with bed slabs	No.	25		
6	Providing and fixing M. S. M. rails 6′′ long verticles and struts for pin slabs	,,	25		
8	Collection and consolidation of broken field metal with necessary gravel, sand, etc., complete at approaches	C.yd.	25		

P. RAMASWAMY,
Executive Engineer.

HASSAN DIVISION.

Abstract Notification dated 30th April 1940.

The attention of the public is invited to the tender notification in the *Mysore Gazette*, dated 9th May 1940, *vide* pages 1037-1039, Part VI, calling for tenders for "constructing a high level causeway across the Vedavathy Halla or Singapur Halla" at 1-15 of Mudgere-Belur Road. The last date for receipt of tenders is 29th May 1940.

G. SUBBA RAO,
Executive Engineer (In-charge).